

Terms and Conditions for Free Standard installation for Split and Inverter AC (Valid up to 31.03.20)

Dear Customer,
Thank you for choosing  Air conditioner. We are pleased to make a limited period offer for free standard installation on purchase of Select models of Split and Inverter Air conditioners.

Scope of work for Standard Installation.

1. Mounting and installation of indoor unit on wall.
2. Making hole on standard 9" brick wall for copper tubes and wires.
3. Placing the Outdoor unit at suitable location (Without Stand).
4. Supply and fixing of 3mtr Copper pipe and 3mtr 4 Core wire (ODU to IDU alone) 3mtr Tape.
5. Laying of Electrical cable from MCB to ODU (3core cable to be provided by Customer)
6. Laying of PVC drain pipe (Pipe to be provided by Customer)
7. Installation of Stabilizer – (Stabilizer to be provided by Customer)
8. Commissioning of the unit.

Rates for Additional works to be paid extra by Customer.

1. Installation of ODU Stand if required:
 - i. ODU stand supply and installation @ Rs.750/- +GST.
 - ii. If ODU stand supplied by customer, only Installation @ Rs.200 +GST
2. Extra interconnecting pipe if required @ Rs.650/Rs.850 +GST per meter. (Refrigerant Pipe +Nitrile rubber Insulation+ tape)
3. Extra Electrical cable if required @ Rs.85 +GST per meter
4. Supply & installation of PVC drain pipe @ Rs.75 +GST per meter
5. Wall chiseling /chipping, if required for concealed piping rates at actuals.
6. Core drilling for beam/concrete wall if required rates at actuals.
7. Dismantling of OLD unit @Rs.750/- +GST.

Note: -

1. Customer has to provide electrical incoming power supply with suitable MCB within one meter of unit location.
2. Any Work not listed in Standard Installation, scaffolding, providing Ladder, Civil works will all be in Customer Scope of work.
3. No reimbursement will be given if free installation offer is not availed.

SSD / SF Name and Address seal:

Call no.:- _____

Customer acknowledgement for additional works.				
S.No	JOB DESCRIPTION	RATE in Rs. per Meter	Qty / RMT	Total Amt in Rs.
Standard Installation				
1	Standard Installation as explained above in Scope of work.	Free	3 Mts	Free
Rates for Additional works to be paid extra by Customer				
2.i	Copper pipe with Insulation material,tape, supply and labour charges for laying upto 1.5 Tr	650		
2.ii	Copper pipe with Insulation material, tape, supply and labour charges for laying upto 2.0/3.0/4.0 Tr.	850		
3	Supply and laying of Electrical 3/4 Core Cable	85		
4	ODU Stand supply and fixing / Only fixing	750 / 200		
5	Drain Pipe supply and fixing	75		
6	Dismantling of OLD/ Existing Split AC unit	750		
Under customer scope or Actual				
7	Wall chiseling /chipping	ACTUAL		
8	Beam/Concrete Wall Core drilling	ACTUAL		
9	Miscellaneous (Please specify)	ACTUAL		
			Sub Total	
			GST Tax @ 18%	
			Total	

Technician Name:-_____ Signature:_____

Customer Name:-_____ Mobile no _____

Customer Signature:-_____ Date:-_____